



TOF CABLING:

16 Total Bundles: 8HV(Red), 8 Signal(Beige)

Each Column Represents a bundle, each matching pair of HV+Signal bundles will enter the cable manager from its corner

The Bundles will be staggered on the detector side(BNC and SHV) such that the cable will terminate to each PMT location with minimal manipulation of bundle

Two ~24" leads will exit the bundle every ~5", for a total staggered termination length of ~50"

8 Bundles will be staggered in ascending order, and 8 Bundles will be staggered in descending order as labeled in the Columns

*TOF view from Upstream looking DownStream